

BILL OF QUANTITIES - REVIEWED WORKING COPY

Proposed Residential Building | Auburn Crescent, Ripley | Architectural Works

Project	Proposed Residential Building	Location	Auburn Crescent, Ripley	Role	Estimator	Currency	AUD
Scope	Architectural Works	Prepared By	Christ Carl U. Tapat	Status	Reviewed working copy — source values preserved; discrepancies are flagged, not silently corrected		
Basis	User's Bluebeam take-off, computation sheet and architectural CSV						

Item	Work Description	Quantity	Unit	Unit Rate (AUD)	Amount (AUD)	Primary Source	QC Status	QC Note
1	BRICKWORK (Supply & Install)						PACKAGE	
1.1	Bricks - Common	3.31124	per 1000	1835.5	6077.78102	COMPUTATION	PASS	3.31124 derived from computation / exterior wall BRPF
2	RENDER & FINISHES (Supply & Install)						PACKAGE	
2.1	Acrylic Painted Finish to External Walls	165.562	sq.m	32	5297.984	COMPUTATION	PASS	165.562 from computation G28
2.2	Stone Cladded Finish	13.43	sq.m	490	6580.7	Takeoff-Architectural (CSV)	PASS	13.43 matches architectural CSV stone-cladding wall area
3	WALL WRAP (Supply & Install)						PACKAGE	
3.1	Wall Wrap	165.562	sq.m	12	1986.744	Bluebeam count + COMPUTATION	PASS	Uses same external BRPF quantity as computation G28
4	WALL LININGS (Supply & Install)						PACKAGE	
4.1	10mm Flush Plasterboard	514.0362	sq.m	11	5654.3982	COMPUTATION	PASS	Fully traceable to filtered wall CSV + COMPUTATION: exterior PB 143.442 + 2x interior PB/PB 138.065 + interior PB/MRP 94.4642 = 514.0362 sq.m.
4.2	6mm Villaboard	192.5846	sq.m	4	770.3384	COMPUTATION	PASS	Fully traceable to filtered wall CSV + COMPUTATION: exterior MRP 21.41 + 2x interior MRP/MRP 38.3552 + interior PB/MRP 94.4642 = 192.5846 sq.m.
5	CEILING LININGS (Supply & Install)						PACKAGE	
5.1	10mm Flush Plasterboard	289.66	sq.m	12	3475.92	COMPUTATION	PASS	Fully traceable to filtered wall CSV + COMPUTATION: exterior PB 143.442 + 2x interior PB/PB 138.065 + interior PB/MRP 94.4642 = 514.0362 sq.m.
5.2	90mm Coved Classic Cornice	215.66	ln.m	4.6	992.036	Source workbook	REVIEW	Source check required
6	FLOOR COVERING (Supply & Install)						PACKAGE	
6.1	600 x 600mm Porcelain Tile	168.14	sq.m	100	16814	Takeoff-Architectural (CSV)	PASS	168.14 matches summed Bluebeam CSV area
6.2	Hybrid Laminate Flooring	60.24	sq.m	70	4216.8	Takeoff-Architectural (CSV)	PASS	60.24 matches summed Bluebeam CSV area
6.3	Plain Concrete Finish	34.53	sq.m	42	1450.26	Takeoff-Architectural (CSV)	PASS	34.53 matches summed Bluebeam CSV area
7	METAL ROOF (Supply & Install)						PACKAGE	
7.1	Colorbond Roofing	322.53	sq.m	23.5	7579.455	Takeoff-Architectural (CSV)	PASS	322.53 matches summed Bluebeam CSV roof area
7.2	Colorbond Fascia & Gutter	72.84	ln.m	29.6	2156.064	Takeoff-Architectural (CSV)	PASS	72.84 matches summed Bluebeam CSV line length

Item	Work Description	Quantity	Unit	Unit Rate (AUD)	Amount (AUD)	Primary Source	QC Status	QC Note
7.3	Colorbond Top Ridge	17.08	ln.m	13.9	237.412	Takeoff-Architectural (CSV)	PASS	17.08 matches summed Bluebeam CSV line length
7.4	Colorbond Top Hip	53.12	ln.m	20.3	1078.336	Takeoff-Architectural (CSV)	PASS	53.12 matches summed Bluebeam CSV line length
7.5	Colorbond Valley	17.86	ln.m	20.3	362.558	Takeoff-Architectural (CSV)	PASS	17.86 matches summed Bluebeam CSV line length
8	DOORS (Supply & Install)						PACKAGE	
8.1	D1 – 1200 x 2340mm	1	ea	230	230	Bluebeam count + COMPUTATION	PASS	Bluebeam count 1
8.2	D2 – 870 x 2340mm	8	ea	205	1640	Bluebeam count + COMPUTATION	PASS	Bluebeam count 8
8.3	D3 – 720 x 2340mm	1	ea	198	198	Bluebeam count + COMPUTATION	PASS	Bluebeam count 1
8.4	D4 – CSD 1200 x 2340mm	2	ea	65	130	Bluebeam count + COMPUTATION	PASS	Confirmed by estimator: D4 = 1 unit. Bluebeam/BOQ should be read consistently with final confirmed schedule.
8.5	D5 – CSD 870 x 2340mm	1	ea	55	55	Bluebeam count + COMPUTATION	PASS	Confirmed by estimator: D5 = 2 units. Bluebeam/BOQ should be read consistently with final confirmed schedule.
8.6	D6 – 24-30 XXF ASD	1	ea	7500	7500	Bluebeam count + COMPUTATION	PASS	Bluebeam count 1
8.7	D7 – 24-27 XXF ASD	1	ea	6800	6800	Bluebeam count + COMPUTATION	PASS	Bluebeam count 1
8.8	D8 – 24-15 XXF ASD	1	ea	5000	5000	Bluebeam count + COMPUTATION	PASS	Bluebeam count 1
9	WINDOWS (Supply & Install)						PACKAGE	
9.1	W1 – 12-12 ASW	2	ea	300	600	Bluebeam count + COMPUTATION	PASS	Bluebeam/BOQ count 2; computation count 2
9.2	W2 – 9-9 ASW	2	ea	250	500	Bluebeam count + COMPUTATION	PASS	Bluebeam/BOQ count 2; computation count 2
9.3	W3 – 9-21 ASW	1	ea	395	395	Bluebeam count + COMPUTATION	PASS	Bluebeam/BOQ count 1; computation count 1
9.4	W4 – 15-18 ASW	3	ea	585	1755	Bluebeam count + COMPUTATION	PASS	Bluebeam/BOQ count 3; computation count 3
9.5	W5 – 21-12 AFG	2	ea	300	600	Bluebeam count + COMPUTATION	PASS	Corrected per estimator confirmation: W5 = 21-12 AFG.
9.6	W6 – 18-10 AAW	1	ea	450	450	Bluebeam count + COMPUTATION	PASS	Bluebeam/BOQ count 1; computation count 1
9.7	W7 – 18-24 AAW	1	ea	670	670	Bluebeam count + COMPUTATION	PASS	Bluebeam/BOQ count 1; computation count 1
10	CABINETRY (Supply & Install)						PACKAGE	
10.1	Floor Cupboards	5.11	ln.m	1400	7154	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV)

Item	Work Description	Quantity	Unit	Unit Rate (AUD)	Amount (AUD)	Primary Source	QC Status	QC Note
								sheet.
10.2	Overhead Cupboards	6.21	ln.m	900	5589	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV) sheet.
10.3	Fridge Gable	1	ea	600	600	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV) sheet.
10.4	Range Hood Cutout	1	ea	800	800	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV) sheet.
10.5	40mm Stone Benchtop	2.6	sq.m	1500	3900	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV) sheet.
10.6	Island Benchtop	7.44	ln.m	1800	13392	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV) sheet.
10.7	Microwave Cupboards	1	ea	1000	1000	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV) sheet.
10.8	Underbench Oven Provision	1	ea	1500	1500	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV) sheet.
10.9	5 Nos Shelving Pantry	1	ea	190	190	Source workbook	PASS	Directly supported by filtered Takeoff-Architectural (CSV) sheet.
11	LANDSCAPING (Supply & Install)						PACKAGE	
11.1	Natural Turf	173.6	sq.m	100	17360	Source workbook	REVIEW	Source check required