

ESTIMATE QUALITY CONTROL - REVIEWED

Proposed Residential Building | Architectural Works | Christ Carl U. Tapat

Project	Proposed Residential Building	Scope	Architectural Works
Prepared By	Christ Carl U. Tapat		

QC Check	Evidence / Calculation	Expected / Reference	Result	Status	Action
Bluebeam measurement evidence	Calibration + area/length/count screenshots supplied	Evidence exists for representative take-off workflow	Screenshots supplied	PASS	Retain in portfolio
Floor covering reconciliation	168.14 + 60.24 + 34.53	262.91 sq.m	262.91 sq.m	PASS	No action
Landscape reconciliation	173.11 + 0.49	173.60 sq.m	173.60 sq.m	PASS	No action
Roofing area reconciliation	CSV sum of Colorbond Roofing	322.53 sq.m	322.53 sq.m	PASS	No action
Fascia & gutter reconciliation	CSV line-length sum	72.84 lm	72.84 lm	PASS	No action
Ridge / hip / valley reconciliation	CSV line-length sums	17.08 / 53.12 / 17.86 lm	Matches BOQ	PASS	No action
Ceiling lining reconciliation	CSV ceiling area sum	289.66 sq.m	289.66 sq.m	PASS	Source sheet screenshot displays 289.67 sq.m due rounding
Cornice reconciliation	CSV cornice line-length sum	215.66 lm	215.66 lm	PASS	No action
Door schedule D4/D5	Bluebeam markup vs COMPUTATION sheet	D4=1, D5=2	Confirmed by estimator	PASS	No unresolved count discrepancy; final confirmed counts are D4=1 and D5=2.
Window W5 label	BOQ/Bluebeam vs COMPUTATION	W5 = 21-12 AFG	Confirmed	PASS	Final window identifier matches the filtered Takeoff-Architectural (CSV) and computation sheet.
Wall lining formulas	COMPUTATION formulas feed BOQ	CSV + COMPUTATION formulas	514.0362 and 192.5846 sq.m	PASS	Formula path verified directly against filtered wall take-off rows.
BOQ total arithmetic	Sum of all package subtotals	AUD 142,738.79	AUD 142,738.79	PASS	No action
RFI readiness	Internal discrepancies identified	Each material discrepancy documented	2 items identified	PASS	Use demonstration RFI